



KARPAGA VINAYAGA EDUCATIONAL TRUST

SHEET 8 OF 8

SPECIFICATIONS:

FOUNDATION CONCRETE IN RCC 1:4:8 OVER SAND FILLING
 SAND FILLING FOR BASEMENT AND BELOW FOUNDATION
 BRICK WORK IN CM 1:6 USING CLASS ONE BRICKS

ALL RCC ITEMS IN DC 1:1.53 WITH NECESSARY REINFORCEMENT
 FLOORING CONCRETE IN RCC 1:4:8 FINISHING WITH TILES
 ROOF SHALL BE OF RCC SLAB IN RCC 1:1.53 AND AC SHEET
 ROOFING WITH STEEL TRUSS & PURLINS AS SHOWN

PLASTERING IN CM 1:4 FINISHING WITH WHITE AND COLOUR WASH
 JOINERY IN BEST COUNTRYTEAK WOOD AND STEEL GRILL WORKS

JOINERY DETAILS

C/G	-COLLAR GATE	-1.52 x 2.13
D	-DOUBLE DOOR	-0.94 x 2.13
D1	-DOOR	-0.76 x 2.13
D2	-DOUBLE DOOR	-1.81 x 2.13
D3	-DOOR	-1.06 x 2.13
W1	-WINDOW	-1.83 x 1.22
W2	-WINDOW	-0.91 x 1.22
V3	-VENTILATOR	-2.44 x 0.60
V2	-VENTILATOR	-0.76 x 0.60
V1	-VENTILATOR	-0.94 x 0.60

**NURSING COLLEGE FLOOR PLANS
ELEVATION & SECTION**

AREA DETAILS

GROUND FLOOR AREA	1143.96	SQ.M
FIRST FLOOR AREA	1078.89	
SECOND FLOOR AREA	1078.89	
THIRD FLOOR AREA	1078.89	
Total	4380.63	

COLOUR INDEX:

EXISTING SHOWN

PROPOSED SHOWN

ROAD SHOWN

BOUNDARY SHOWN

OWNER:

LICENSED SUPERVISOR:

REGISTERED ARCHITECT:

SCALE = 1 : 150

DATE: 01/11/2018

PROJECT: NURSING COLLEGE

LOCATION: KARPAGA VINAYAGA EDUCATIONAL TRUST

Handwritten notes in Tamil and English, including dates and project details.